The Day-Burdette House is moderately significant in architecture as an example of the Queen Anne style of the early 20th century. The exterior retains much of its original character, although the roof has been replaced with modern composition material and a two-story addition was built in the The exterior cladding is german siding and a two-story 1940's or 1950's. polygonal bay is at the southwest corner. Shingled gables are at the ends of the house and over the polygonal bay. An additional gable rises from the roof of the rear wing extending from the southwest corner. The windows are 1/1 with replacement shutters. A dentil cornice edges the eaves and the porches on the southeast and south elevations have turned columns and balustrades with scroll-sawn brackets. The interior has been altered, but the basic two-room plan with a center hall remains intact, as do the molded architraves and bull's eye corner blocks of the trim. The stair has a turned newel and balustrade. Small molded mantelpieces built for heating stoves are in the main rooms. The compact design and unified decoration of the house strongly suggest that it was built from a design in a builder's catalog or other published architectural The house was probably built about 1905-1910 by Harry T. Day. In 1912, plan. Perry G. and Lucinda Burdette purchased the house and it remained in the possession of their descendants until 1980.

F-5-109 Day-Burdette House Mt. Airy Frederick County

HISTORIC CONTEXT:

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

Geographic Organization: Piedmont (Harford, Baltimore, Carroll, Frederick, Howard, Montgomery Counties, and Baltimore City)

Chronological/Development Period: Industrial/Urban Dominance, A.D. 1870-1930

Prehistoric/Historic Period Themes:
Architecture, Landscape Architecture and Community Planning

Resource Types:

Category: Building

Historic Environment: Rural

Historic Function and Use:
Domestic/single dwelling/residence

Known Design Source: None



Magi No.

DOE __yes x_no

				····
1. Nam	e (indicate pa	referred name)		
historic Da	ay-Burdette House			
and/or common				
2. Loca	ation			
street & number	13616 Penn Shop	o Road	_	not for publication
city, town	Mt. Airy	_X vicinity of	congressional district	6th
	yland	county	Frederick	
	sification			
Category district _X_ building(s) structure site object	Ownership public private both Public Acquisition in process being considered not applicable	Status X occupied unoccupied work in progress Accessible yes: restricted pes: unrestricted no	Present Use agriculture commercial educational entertainment government industrial military	museum park x private residence religious scientific transportation other:
4. Own	er of Prope	rty (give names a	nd mailing addresse	es of <u>all</u> owners)
name Jeri	ry & Solveig L. Smi	th		
street & number	24300 Kakae Dri	.ve	telephone n	10.:
city, town	Damascus	state	and zip code MD	20872
	ation of Leg	al Descripti	on	
courthouse, regi	stry of deeds, etc.	rederick County Cou	rthouse	liber 1670
street & number	100 W. Patrick	Street		folio 218
city, town	Frederick		state	MD 21701
6. Rep	resentation	in Existing	Historical Surv	<i>r</i> eys
title				
date			federal sta	te county loca
_epository for si	urvey records			
city, town			state	
				

7. Description

Survey No.

F-5-109

Condition excellent deteriorated X good ruins fair unexposed	Check one unaltered altered	Check one x original site moved date of move	
--	-----------------------------	--	--

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

CONTRIBUTING RESOURCE COUNT: 1

The Day-Burdette House is a two-story frame Queen Anne style dwelling built about 1905-1910 on the north side of Penn Shop Road about 1 mile southwest of the intersection of Ridge Road (Md. 27) near Mt. Airy, Frederick County, Maryland. The house has the typical exterior characteristics of the style, with a polygonal two-story bay, shingled gables, porches with turned columns and scroll-sawn brackets, and german siding. The principal elevation faces southeast and the house is one of a line of dwellings along the north side of Penn Shop Road, most of which were built from the 1950's to the 1990's. The north elevation of the house faces open agricultural fields. The date of the house is based on architectural details and land records.

The southeast elevation of the house has three bays, with a polygonal two-story bay at the southwest corner and the two other bays are sheltered under a one-story The exterior is covered with german siding, except for the gables in each elevation, which are covered with patterned shingles. Arched windows with 2/2 sash are centered in each gable. The entrance is in the center bay and has a glass panel door with a narrow transom and sidelights. The windows are 1/1 with modern The porch has turned columns and balusters with scroll-sawn replacement shutters. brackets. The roof is covered with composition material, a replacement of t¹ Two off-center chimneys rise from the roof. A dentil cornice ornaments t house and the porch roof. On the northwest corner of the house is a short rear wing with a one-story side porch facing south. This porch also has turned columns and brackets. Both the front and side porches have concrete decks, replacing the The rear wing has an additional shingled gable above the original wood decks. second story facing south. The foundation of the house is stone. At the northeast corner is a two-story addition on a concrete foundation. An enclosed shed porch on the north elevation and this porch appear to have been added in the 1940's or 1950's. An exterior concrete block chimney stack rises on the north elevation.

The interior spaces of the house are small in proportion to the height of the building, with a narrow center hall flanked by two rooms in the first story and a single room in the original wing as the kitchen. Much of the wood trim remains at the door and window surrounds, with bull's eye corner blocks and molded architraves. The staircase has a turned newel and balustrade. Simple wood mantelpieces in the two main first story rooms indicate that the house was designed for stove heat. The rear wing and the addition have been much remodeled in recent years, although a winding enclosed stair at the northwest corner of the wing remains in place.

1400–1499 1500–1599 — 1600–1699 — 1700–1799 — 1800–1899	agriculture X architecture	• •	law literature military music	science sculpture social/ humanitarian theater
Specific date	s C. 1910	Builder/Architect		•
Арр	licable Criteria:A and/or licable Exception:, el of Significance:	A _B _C _D		

Survey No.

F-5-109

8. Significance

Prepare both a summary paragraph of significance and a general statement of history and support.

The Day-Burdette House is moderately significant in architecture for the exterior design of the house, a little-altered vernacular Queen Anne style dwelling built about 1905-1910, possibly according to a published design from a builder's catalog. The construction history has not been determined, but land records show that Harry T. Day purchased the approximately 2-acre lot in 1903 for \$225 and sold it to Perry G. and Lucinda Burdette in 1912 for \$1500. The house was probably built during the 9 years between the two transactions. Its compact design and unified decoration strongly suggest that it is an example of a published design, perhaps from a builder's catalog or newspaper offering. Both of these sources of rehitectural plans were frequently used in the early 20th century. The house mained in the Burdette family until 1980.

9. Major Bibliographical References

Survey No. F-5-109

Land Records of Frederick County

10. Geog	graphical Data		
Acreage of nominate Quadrangle name UTM References d		ences	Quadrangle scale 1:24000
A Zone Easting	Northing	B Zone Easting	Northing
C		D	
-	lescription and justification		
	n Tax Map 99, Parcel 2		
	Tax Map 99, Parcel 2 counties for properties overl	apping state or county be	oundaries code
List all states and	counties for properties over		
List all states and state	counties for properties overl	county	code
List all states and state state 11. Form	counties for properties overl code code	county	code
List all states and state state 11. Form	counties for properties overles code code	county county es Surveyor	code
List all states and state state 11. Form	counties for properties overloade code code Prepared By t L. Davis, Historic Site	county county es Surveyor	code


The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust Shaw House 21 State Circle Annapolis, Maryland 21401 (301) 269-2438 MARYLAND HISTORICAL TRUST DHCP/DHCD 100 COMMUNITY PLACE CROWNSVILLE, MD 21032-2023 -514-7600

Liber/Folio	Grantee Grantee	Grantor	Lot Size, Description, Original Tracts, Miscellaneous	Cost
1670/218 14 Sept 90	Jeary & Solving & Solving	Patsy C. Cochran & Mark B. Buyton	1. 8401 a.	#153,000
116 1/671 30 Mov 81	Palsy C. Buxtor and her son mark B. Buxton	Miltona. 4 Polly-ambract		\$91,250
1135/740 22 Dec 80	miltona.	Shirley & Loque Elleam Reppeor many Moune Barle	er	,
136/367 190ct65	Shiley a Logue	Kalph I Hoffm.	orn.	
736/365 190ct 65	Ralph Is Hoff mar, trustee		Le part of "Burli's Lat" 1 a., 1 R., 3 sq. p.	1.4
370/535 6 Jul 29	Samuel & Bertha Budette	Lucinda Budell	e part of Burk's Lot"	\$2500
302/197 22 May 1:	Perry G. 4 2 Lucinda Budet	Harry J. + Effick. Day		\$1500
DHH 17/61. 7 Sept 03	0	§	part of "Burkes Lat" 10., 1R. 30 sq. p.	#225
DHH 17/6/6 30 gul 188	Lausen Butler	Thos. J. + Leah Day	part of Benke's Lat" 10., 12. 30 sq. fs.	#150
#I				- 121 - 134 x





7 = 5 = Kro71 Louis Filme Fie France Photo: Tanet-Law. 1718 #2 44



Date Break wit 4 Bonce Frederich County Lienten - His Silver Ifen is He Int



F. 5 = 19 1 July Englove Elemen Frederick Contr August Be Zillin Eller Gran march Trailing 12 FE 12 C